

Bruhat Bangalore Mahanagara Palike
Executive Engineer Yelahanka Division

NAME OF WORK:- Modified Estimate For Drilling of borewells & Providing pipe line and supply of drinking water to public in Harohalli, Nagenahalli, Kenchanahalli, Doddabettahalli, Chikkabettahalli and Ananthpura village areas in ward No 01 and Ward No 03 of Yelahanka Division.

No 03 of Yelahanka Division									
Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	NEW BOREWELL(A)								
1	Geophysical investigation at site for sinking borewells for Providing drinking water to the habitation either through the Hand Pump MWS or P.W.S.S, by vertical electrical sounding by adopting Venner or Schlumbergers's method, including reconnaissance survey of geological formation. Geophysical investigation of existing ground water in the vicinity, its quality, quantity and acceptability of the users, indicating the location of the site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instruments and accessories to work site, engaging technical personal and labour required etc. NOTE: 1) Additional rate on item 1&2 is allowed for drilling in over burden and fixing Casing pipes beyond 20 M (for fixing Casing pipes only) a) Above 20 M and upto 30 M - 15%, b) Above 30 M - 30% (Measurement of overburden is restricted to the depth of casing pipe fixed excluding initial depth of 20M and								
	For Bore Well								
	1st Main Rd Maruthi badavane		1				1.00		
	Ambha Bhavani Nagara 2nd Main 2nd Cross		1				1.00		
	8th Cross Rd BHEL Layout		1				1.00		
	6th Cross Sainagara 3rd Phase		1				1.00		
	1st Main Rd Vijaya Bank Layout		1				1.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1				1.00		
	1st Main Ayyappa Layout		1				1.00		
	Burial Ground Vishwanagara Main Rd		1				1.00		
	1st Main Chandrappa Layout		1				1.00		
	9th Main 4th Cross Rd Adtiyanagara		1				1.00		
	1st Main Rd Eshwari Layout		1				1.00		
	Anugraha Layout[Avekanagar Layout		1				1.00		
			1				1.00		
	Balaji Enclave 1st Cross Rd		1				1.00		
	Nisargha Layout 10th Main Rd		1				1.00		
	CRPF Compound Near Govt School Ananthapura		1				1.00		
	Mahalakshmi Layout Main Rd		1				1.00		
	Ambhabhavani Layout 6th Cross Rd		1				1.00		
	Hariraja Layout 3rd Cross Rd		1				1.00		
	Balaji Layout 4th Cross Rd		1				1.00		
	Brundavana Layout 1st Main Rd 1st Cross		1				1.00		
	6th Cross AMS NEW Extension		1				1.00		
	3rd Cross Adtiyanagaraa		1				1.00		
	Cauvery Layout 2nd Main Rd		1				1.00		

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
		Each	1				1.00		
	Approved Amount	5784.98					25.00	5784.98	144624.50
2	Sinking of Borewell of 165mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern upto 20 m. Fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicle, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (Excluding cost of casing pipes, collars, 0-50mtrs								
		Mtr							
	1st Main Rd Maruthi Layout		1	50.00			50.00		
	Ambha Bhavani Nagara 2nd Main		1	50.00			50.00		
	8th Cross Rd BHEL Layout		1	50.00			50.00		
	6th Cross Sainagara 3rd Phase best		1	50.00			50.00		
	1st Main Rd Vijaya Bank Layout		1	50.00			50.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	50.00			50.00		
	1st Main Ayyappa Layout		1	50.00			50.00		
	Burial Ground Vishwanagara Main Rd		1	50.00			50.00		
	1st Main Chandrappa Layout		1	50.00			50.00		
	9th Main 4th Cross Rd Adtiyanagara		1	50.00			50.00		
	1st Main Rd Eshwari Layout		1	50.00			50.00		
	Anugraha Layout[Avekanagar Layout]		1	50.00			50.00		
			1	50.00			50.00		
	Balaji Enclave 1st Cross Rd		1	50.00			50.00		
	Nisargha Layout 10th Main Rd		1	50.00			50.00		
	CRPF Compound Near Govt School Ananthapura		1	50.00			50.00		
	Mahalakshmi Layout Main Rd		1	50.00			50.00		
	Ambhabhavani Layout 6th Cross Rd		1	50.00			50.00		
	Hariraja Layout 3rd Cross Rd		1	50.00			50.00		
	Balaji Layout 4th Cross Rd		1	50.00			50.00		
	Brundavana Layout 1st Main Rd 1st Cross		1	50.00			50.00		
	6th Cross AMS NEW Extension		1	50.00			50.00		
	3rd Cross Adtiyanagaraa		1	50.00			50.00		
	Cauvery Layout 2nd Main Rd		1	50.00			50.00		
			1	50.00			50.00		
							1250.00	404.77	505962.50
	Approved Amount	404.77							
3	50-100mtrs(P.139, I.No-12.1.2) Vol-5 BWSSB.SR 2023-24								
		Mtr							
	1st Main Rd Maruthi Layout		1	50.00			50.00		
	Ambha Bhavani Nagara 2nd Main		1	50.00			50.00		
	8th Cross Rd BHEL Layout		1	50.00			50.00		
	6th Cross Sainagara 3rd Phase best		1	50.00			50.00		
	1st Main Rd Vijaya Bank Layout		1	50.00			50.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	50.00			50.00		
	1st Main Ayyappa Layout		1	50.00			50.00		

T + ಮುಖ್ಯ ಅಭಿಯಂತರರು
 (ಮುಖ್ಯ)

ಮುಖ್ಯ ಅಭಿಯಂತರರು
 ಬಹುಶಃ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

SI No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
144624.50	Burial Ground Vishwanagara Main Rd		1	50.00			50.00		
	1st Main Chandrappa Layout		1	50.00			50.00		
	9th Main 4th Cross Rd Adtiyanagara		1	50.00			50.00		
	1st Main Rd Eshwari Layout		1	50.00			50.00		
	Anugraha Layout[Avekanagar Layout		1	50.00			50.00		
			1	50.00			50.00		
	Balaji Enclave 1st Cross Rd		1	50.00			50.00		
	Nisargha Layout 10th Main Rd		1	50.00			50.00		
	CRPF Compound Near Govt School Ananthapura		1	50.00			50.00		
	Mahalakshmi Layout Main Rd		1	50.00			50.00		
	Ambhabhavani Layout 6th Cross Rd		1	50.00			50.00		
	Hariraja Layout 3rd Cross Rd		1	50.00			50.00		
	Balaji Layout 4th Cross Rd		1	50.00			50.00		
	Brundavana Layout 1st Main Rd 1st Cross		1	50.00			50.00		
	6th Cross AMS NEW Extension		1	50.00			50.00		
	3rd Cross Adtiyanagaraa		1	50.00			50.00		
	Cauvery Layout 2nd Main Rd		1	50.00			50.00		
			1	50.00			50.00		
Approved Amount		507.61					1250.00	507.61	634512.50
4	100-150mtrs (P.139, I.No-12.1.3) Vol-5 BWSSB.SR 2023-24	Mtr							
	1st Main Rd Maruthi Layout		1	50.00			50.00		
	Ambha Bhavani Nagara 2nd Main		1	50.00			50.00		
	8th Cross Rd BHEL Layout		1	50.00			50.00		
	6th Cross Sainagara 3rd Phase best		1	50.00			50.00		
	1st Main Rd Vijaya Bank Layout		1	50.00			50.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	50.00			50.00		
	1st Main Ayyappa Layout		1	50.00			50.00		
	Burial Ground Vishwanagara Main Rd		1	50.00			50.00		
	1st Main Chandrappa Layout		1	50.00			50.00		
	9th Main 4th Cross Rd Adtiyanagara		1	50.00			50.00		
	1st Main Rd Eshwari Layout		1	50.00			50.00		
	Anugraha Layout[Avekanagar Layout		1	50.00			50.00		
			1	50.00			50.00		
	Balaji Enclave 1st Cross Rd		1	50.00			50.00		
	Nisargha Layout 10th Main Rd		1	50.00			50.00		
	CRPF Compound Near Govt School Ananthapura		1	50.00			50.00		
	Mahalakshmi Layout Main Rd		1	50.00			50.00		
	Ambhabhavani Layout 6th Cross Rd		1	50.00			50.00		
	Hariraja Layout 3rd Cross Rd		1	50.00			50.00		
	Balaji Layout 4th Cross Rd		1	50.00			50.00		
	Brundavana Layout 1st Main Rd 1st Cross		1	50.00			50.00		
	6th Cross AMS NEW Extension		1	50.00			50.00		

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	3rd Cross Adtiyanagaraa		1	50.00			50.00		
	Cauvery Layout 2nd Main Rd		1	50.00			50.00		
			1	50.00			50.00		
	Approved Amount	539.33					1250.00	539.33	674162.50
5	150-200mtrs ((P.139, I.No-12.1.4) Vol-5 BWSSB.SR 2023-24	Mtr							
	1st Main Rd Maruthi Layout		1	50.00			50.00		
	Ambha Bhavani Nagara 2nd Main		1	50.00			50.00		
	8th Cross Rd BHEL Layout		1	50.00			50.00		
	6th Cross Sainagara 3rd Phase best		1	50.00			50.00		
	1st Main Rd Vijaya Bank Layout		1	50.00			50.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	50.00			50.00		
	1st Main Ayyappa Layout		1	50.00			50.00		
	Burial Ground Vishwanagara Main Rd		1	50.00			50.00		
	1st Main Chandrappa Layout		1	50.00			50.00		
	9th Main 4th Cross Rd Adtiyanagara		1	50.00			50.00		
	1st Main Rd Eshwari Layout		1	50.00			50.00		
	Anugraha Layout[Avekanagar Layout		1	50.00			50.00		
			1	50.00			50.00		
	Balaji Enclave 1st Cross Rd		1	50.00			50.00		
	Nisargha Layout 10th Main Rd		1	50.00			50.00		
	CRPF Compound Near Govt School Ananthapura		1	50.00			50.00		
	Mahalakshmi Layout Main Rd		1	50.00			50.00		
	Ambhabhavani Layout 6th Cross Rd		1	50.00			50.00		
	Hariraja Layout 3rd Cross Rd		1	50.00			50.00		
	Balaji Layout 4th Cross Rd		1	50.00			50.00		
	Brundavana Layout 1st Main Rd 1st Cross		1	50.00			50.00		
	6th Cross AMS NEW Extension		1	50.00			50.00		
	3rd Cross Adtiyanagaraa		1	50.00			50.00		
	Cauvery Layout 2nd Main Rd		1	50.00			50.00		
			1	50.00			50.00		
	Approved Amount	625.76					1250.00	625.76	782200.00
6	200-250mtrs (P.139, I.No-12.1.5) Vol-5 BWSSB.SR 2023-24	Mtr							
	1st Main Rd Maruthi Layout		1	50.00			50.00		
	Ambha Bhavani Nagara 2nd Main		1	50.00			50.00		
	8th Cross Rd BHEL Layout		1	50.00			50.00		
	6th Cross Sainagara 3rd Phase best		1	50.00			50.00		
	1st Main Rd Vijaya Bank Layout		1	50.00			50.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	50.00			50.00		
	1st Main Ayyappa Layout		1	50.00			50.00		
	Burial Ground Vishwanagara Main Rd		1	50.00			50.00		

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	1st Main Chandrappa Layout		1	50.00			50.00		
	9th Main 4th Cross Rd Adtiyanagara		1	50.00			50.00		
	1st Main Rd Eshwari Layout		1	50.00			50.00		
	Anugraha Layout[Avekanagar Layout		1	50.00			50.00		
			1	50.00			50.00		
	Balaji Enclave 1st Cross Rd		1	50.00			50.00		
	Nisargha Layout 10th Main Rd		1	50.00			50.00		
	CRPF Compound Near Govt School Ananthapura		1	50.00			50.00		
	Mahalakshmi Layout Main Rd		1	50.00			50.00		
	Ambhabhavani Layout 6th Cross Rd		1	50.00			50.00		
	Hariraja Layout 3rd Cross Rd		1	50.00			50.00		
	Balaji Layout 4th Cross Rd		1	50.00			50.00		
	Brundavana Layout 1st Main Rd 1st		1	50.00			50.00		
	6th Cross AMS NEW Extension		1	50.00			50.00		
	3rd Cross Adtiyanagaraa		1	50.00			50.00		
	Cauvery Layout 2nd Main Rd		1	50.00			50.00		
			1	50.00			50.00		
							1250.00	734.06	917575.00
	Approved Amount		734.06						
7	250-300mtrs (P.139, I.No-12.1.6) Vol-5 BWSSB.SR 2023-24	Mtr							
	1st Main Rd Maruthi Layout		1	50.00			50.00		
	Ambha Bhavani Nagara 2nd Main		1	50.00			50.00		
	8th Cross Rd BHEL Layout		1	50.00			50.00		
	6th Cross Sainagara 3rd Phase best		1	50.00			50.00		
	1st Main Rd Vijaya Bank Layout		1	50.00			50.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	50.00			50.00		
	1st Main Ayyappa Layout		1	50.00			50.00		
	Burial Ground Vishwanagara Main Rd		1	39.00			39.00		
	1st Main Chandrappa Layout		1	50.00			50.00		
	9th Main 4th Cross Rd Adtiyanagara		1	50.00			50.00		
	1st Main Rd Eshwari Layout		1	25.00			25.00		
	Anugraha Layout[Avekanagar Layout		1	50.00			50.00		
			1	50.00			50.00		
	Balaji Enclave 1st Cross Rd		1	50.00			50.00		
	Nisargha Layout 10th Main Rd		1	50.00			50.00		
	CRPF Compound Near Govt School Ananthapura		1	50.00			50.00		
	Mahalakshmi Layout Main Rd		1	50.00			50.00		
	Ambhabhavani Layout 6th Cross Rd		1	50.00			50.00		
	Hariraja Layout 3rd Cross Rd		1	50.00			50.00		
	Balaji Layout 4th Cross Rd		1	50.00			50.00		
	Brundavana Layout 1st Main Rd 1st		1	50.00			50.00		
	6th Cross AMS NEW Extension		1	50.00			50.00		
	3rd Cross Adtiyanagaraa		1	50.00			50.00		
	Cauvery Layout 2nd Main Rd		1	50.00			50.00		
			1	50.00			50.00		

674162.50

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Approved Amount		809.55				1214.00	809.55	982793
8	300-350mtrs (P.139, I.No-12.1.7) Vol-5 BWSSB.SR 2023-24	Mtr							
	1st Main Rd Maruthi Layout		1	50.00			50.00		
	Ambha Bhavani Nagara 2nd Main		1	41.00			41.00		
	8th Cross Rd BHEL Layout		1	50.00			50.00		
	6th Cross Sainagara 3rd Phase best		1	50.00			50.00		
	1st Main Rd Vijaya Bank Layout		1	50.00			50.00		
	1st Main Rd Annapurneshwari		1	50.00			50.00		
	Nagara[Opp To Sambram Clg]		1	35.00			35.00		
	1st Main Ayyappa Layout		1	50.00			50.00		
	1st Main Chandrappa Layout		1	50.00			50.00		
	9th Main 4th Cross Rd Adtiyanagara		1	50.00			50.00		
	Anugraha Layout[Avekanagar Layout		1	50.00			50.00		
			1	50.00			50.00		
	Balaji Enclave 1st Cross Rd		1	50.00			50.00		
	Nisargha Layout 10th Main Rd		1	50.00			50.00		
	CRPF Compound Near Govt School		1	50.00			50.00		
	Ananthapura		1	47.00			47.00		
	Mahalakshmi Layout Main Rd		1	20.00			20.00		
	Ambhabhavani Layout 6th Cross Rd		1	50.00			50.00		
	Hariraja Layout 3rd Cross Rd		1	50.00			50.00		
	Balaji Layout 4th Cross Rd		1	36.00			36.00		
	Brundavana Layout 1st Main Rd 1st		1	36.00			36.00		
	6th Cross AMS NEW Extension		1	50.00			50.00		
	3rd Cross Adtiyanagaraa		1	50.00			50.00		
	Cauvery Layout 2nd Main Rd		1	36.00			36.00		
			1	50.00			50.00		
	Approved Amount		949.58				1051.00	949.58	998008.58
9	350 to 400 mtr (P.139, I.No- 12.1.8) Vol-5 BWSSB.SR 2023-24	Mtr							
	1st Main Rd Maruthi Layout		1	16.00			16.00		
	8th Cross Rd BHEL Layout		1	46.00			46.00		
	6th Cross Sainagara 3rd Phase best		1	46.00			46.00		
	1st Main Chandrappa Layout		1	9.00			9.00		
	9th Main 4th Cross Rd Adtiyanagara		1	15.00			15.00		
	Anugraha Layout[Avekanagar Layout		1	15.00			15.00		
			1	15.00			15.00		
	Balaji Enclave 1st Cross Rd		1	10.00			10.00		
	Nisargha Layout 10th Main Rd		1	2.00			2.00		
	Ambhabhavani Layout 6th Cross Rd		1	2.00			2.00		
	Hariraja Layout 3rd Cross Rd		1	24.00			24.00		
	6th Cross AMS NEW Extension		1	14.00			14.00		
	3rd Cross Adtiyanagaraa		1	11.00			11.00		
			1	15.00			15.00		
							240.00	1025.06	246014.40

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Approved Amount	1025.06							
10	Supply of ISI mark 175mm nominal bore, plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest ammendments, electrical resistance welded steel tubes, material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends. threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes all shall be responsibly free from defects. The tubes shall be responsible straight end should be with ISI								
		Mtr							
	For Bore Well								
	1st Main Rd Maruthi Layout		1	57.00			57.00		
	Ambha Bhavani Nagara 2nd Main		1	54.00			54.00		
	8th Cross Rd BHEL Layout		1	63.00			63.00		
	6th Cross Sainagara 3rd Phase best		1	60.00			60.00		
	1st Main Rd Vijaya Bank Layout		1	60.00			60.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	56.00			56.00		
	1st Main Ayyappa Layout		1	60.00			60.00		
	Burial Ground Vishwanagara Main Rd		1	56.00			56.00		
	1st Main Chandrappa Layout		1	79.00			79.00		
	9th Main 4th Cross Rd Adtiyanagara		1	58.00			58.00		
	1st Main Rd Eshwari Layout		1	56.00			56.00		
	Anugraha Layout[Avekanagar Layout		1	58.00			58.00		
			1	55.00			55.00		
	Balaji Enclave 1st Cross Rd		1	56.00			56.00		
	Nisargha Layout 10th Main Rd		1	55.00			55.00		
	CRPF Compound Near Govt School Ananthapura		1	60.00			60.00		
	Mahalakshmi Layout Main Rd		1	55.00			55.00		
	Ambhabhavani Layout 6th Cross Rd		1	48.00			48.00		
	Hariraja Layout 3rd Cross Rd		1	60.00			60.00		
	Balaji Layout 4th Cross Rd		1	63.00			63.00		
	Brundavana Layout 1st Main Rd 1st Cross		1	43.00			43.00		
	6th Cross AMS NEW Extension		1	77.00			77.00		
	3rd Cross Adtiyanagaraa		1	51.00			51.00		
	Cauvery Layout 2nd Main Rd		1	45.00			45.00		
			1	50.00			50.00		
							1435.00	2114.67	3034551.45
	Approved Amount	2114.67							
11	PVC pipes of 10 Kg/cm2 for 200mm (P.NO-A-44, SL.No-664) Vol-5 BWSSB.SR 2023-24								
		Mtr							
	For Bore Well								
	1st Main Rd Maruthi Layout		1	8.00			8.00		
	Ambha Bhavani Nagara 2nd Main		1	12.00			12.00		
	1st Main Rd Vijaya Bank Layout		1	12.00			12.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	14.00			14.00		
	1st Main Ayyappa Layout		1	12.00			12.00		

Sl No	Description of work	Unit	Measurement			Qty	Rate	Amount
			No.	L	B	D		
	Burial Ground Vishwanagara Main Rd		1	9.00				
	1st Main Chandrappa Layout		1	10.00			9.00	
	9th Main 4th Cross Rd Adtiyanagara		1	10.00			10.00	
	1st Main Rd Eshwari Layout		1	12.00			10.00	
	Anugraha Layout[Avekanagar Layout		1	12.00			12.00	
	Balaji Enclave 1st Cross Rd		1	12.00			12.00	
	Nisargha Layout 10th Main Rd		1	12.00			12.00	
	CRPF Compound Near Govt School Ananthapura		1	8.00			12.00	
	Mahalakshmi Layout Main Rd		1	10.00			8.00	
	Ambhabhavani Layout 6th Cross Rd		1	9.00			10.00	
	Hariraja Layout 3rd Cross Rd		1	12.00			9.00	
	Balaji Layout 4th Cross Rd		1	14.00			12.00	
	Brundavana Layout 1st Main Rd 1st Cross		1	10.00			14.00	
	3rd Cross Adtiyanagaraa		1	12.00			10.00	
	Cauvery Layout 2nd Main Rd		1	12.00			12.00	
			1	9.00			12.00	
			1	12.00			9.00	
			1	9.00			12.00	
							9.00	
	Approved Amount						240.00	
								1263.55
								303252.00

12 Providing and laying at site of work **MS casing caps** as per IS 1239 (part II) 1982 with all latest amendments if any for any dia. The thickness of plate used for covering one end shall be 3mm (minimum). The dimensions of caps and colars shall be strictly as per IS 1239 (Part-II) 1982 with all amendments including cost of material and labour charges for fixing, if any etc. complete with all lead and lifts and as directed by the Engineer in charge (P.143, I.No-12.34) Vol-5 BWSSB.SR 2023-24

For Bore Well	Each							
1st Main Rd Maruthi Layout								
Ambha Bhavani Nagara 2nd Main		1						
8th Cross Rd BHEL Layout		1				1.00		
6th Cross Sainagara 3rd Phase best		1				1.00		
1st Main Rd Vijaya Bank Layout		1				1.00		
1st Main Rd Annapurneshwari		1				1.00		
Nagara[Opp To Sambram Clg]		1				1.00		
1st Main Ayyappa Layout		1				1.00		
Burial Ground Vishwanagara Main Rd		1				1.00		
1st Main Chandrappa Layout		1				1.00		
9th Main 4th Cross Rd Adtiyanagara		1				1.00		
1st Main Rd Eshwari Layout		1				1.00		
Anugraha Layout[Avekanagar Layout		1				1.00		
		1				1.00		
Balaji Enclave 1st Cross Rd		1				1.00		
Nisargha Layout 10th Main Rd		1				1.00		
CRPF Compound Near Govt School Ananthapura		1				1.00		
Mahalakshmi Layout Main Rd		1				1.00		
Ambhabhavani Layout 6th Cross Rd		1				1.00		
		1				1.00		
						1.00		

77 ಮುಖ್ಯ ಅಭಿಯಂಶಕರು(ಯ.ಎ) ಮುಖ್ಯ ಅಭಿಯಂಶಕರು
 ಬಹು ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

SI No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Hariraja Layout 3rd Cross Rd		1				1.00		
	Balaji Layout 4th Cross Rd		1				1.00		
	Brundavana Layout 1st Main Rd 1st Cross		1				1.00		
	6th Cross AMS NEW Extension		1				1.00		
	3rd Cross Adtiyanagaraa		1				1.00		
	Cauvery Layout 2nd Main Rd		1				1.00		
			1				1.00		
							25.00	179.41	4485.25
	Approved Amount	179.41							
13	Providing, supplying to work site, Submersible Pump Set of 150mm dia suitable for bore well and confirming to IS 8034-2000; 3Phase, SS Bowl & Impeller with Low volt Motor as per specifications, as per necessary ammendments and instructions of engineer incharge of work. 15.00 HP - 120 LPM @ 266 m = 23 STG Outlet Dia - 2.00" [P.153, I.No-13.18.6) Vol-5 BWSSB.SR 2023-24]								
		Each							
	For Bore Well								
	1st Main Rd Maruthi Layout		1				1.00		
	Ambha Bhavani Nagara 2nd Main		1				1.00		
	1st Main Rd Vijaya Bank Layout		1				1.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1				1.00		
	1st Main Ayyappa Layout		1				1.00		
	Burial Ground Vishwanagara Main Rd		1				1.00		
	1st Main Chandrappa Layout		1				1.00		
	9th Main 4th Cross Rd Adtiyanagara		1				1.00		
	1st Main Rd Eshwari Layout		1				1.00		
	Anugraha Layout[Avekanagar Layout		1				1.00		
			1				1.00		
	Balaji Enclave 1st Cross Rd		1				1.00		
	Nisargha Layout 10th Main Rd		1				1.00		
	CRPF Compound Near Govt School Ananthapura		1				1.00		
	Mahalakshmi Layout Main Rd		1				1.00		
	Ambhabhavani Layout 6th Cross Rd		1				1.00		
	Hariraja Layout 3rd Cross Rd		1				1.00		
	Balaji Layout 4th Cross Rd		1				1.00		
	Brundavana Layout 1st Main Rd 1st Cross		1				1.00		
	3rd Cross Adtiyanagaraa		1				1.00		
	Cauvery Layout 2nd Main Rd		1				1.00		
			1				1.00		
							22.00	75861.16	1668945.52
	Approved Amount	75861.16							
14	Supply and delivery of galvanized mild steel tubes of 6mtr standard length heavy duty (C Class) as per IS 1239 (Part-I) 1990 with latest amendments with ISI Mark 50mm [P.155, I.No-13.27.1) Vol-5 BWSSB.SR 2023-24]								
		Each							
	1st Main Rd Maruthi Layout		56				56.00		
	Ambha Bhavani Nagara 2nd Main 2nd Cross		53				53.00		

Sl No	Description of work	Unit	Measurement				Qty	Rate	
			No.	L	B	D			
	1st Main Rd Vijaya Bank Layout		54				54.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		51				51.00		
	1st Main Ayyappa Layout		54				54.00		
	Burial Ground Vishwanagara Main Rd		44				44.00		
	1st Main Chandrappa Layout		55				55.00		
	9th Main 4th Cross Rd Adtiyanagara		56				56.00		
	1st Main Rd Eshwari Layout		42				42.00		
	Anugraha Layout[Avekanagar Layout]		56				56.00		
	Balaji Enclave 1st Cross Rd		48				48.00		
	Nisargha Layout 10th Main Rd		53				53.00		
	CRPF Compound Near Govt School Ananthapura		52				52.00		
	Mahalakshmi Layout Main Rd		51				51.00		
	Ambhabhavani Layout 6th Cross Rd		47				47.00		
	Hariraja Layout 3rd Cross Rd		52				52.00		
	Balaji Layout 4th Cross Rd		56				56.00		
	Brundavana Layout 1st Main Rd 1st Cross		49				49.00		
	3rd Cross Adtiyanagaraa		49				49.00		
	Cauvery Layout 2nd Main Rd		54				54.00		
			49				49.00		
			48				48.00		
	Approved Amount		3336.65				1129.00	3336.65	3767077.85
15	Supply and delivery at site wrought middle steel (galvanized) GI union confirming to IS 1239-II, 1991 with latest amendments if any. For 50 mm dia GI Union (BWSSB SR 2023-24 P-131, I-11.12.6)								
	For Bore Well	Each							
	1st Main Rd Maruthi Layout		1				1.00		
	Ambha Bhavani Nagara 2nd Main		1				1.00		
	1st Main Rd Vijaya Bank Layout		1				1.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1				1.00		
	1st Main Ayyappa Layout		1				1.00		
	Burial Ground Vishwanagara Main Rd		1				1.00		
	1st Main Chandrappa Layout		1				1.00		
	9th Main 4th Cross Rd Adtiyanagara		1				1.00		
	1st Main Rd Eshwari Layout		1				1.00		
	Anugraha Layout[Avekanagar Layout]		1				1.00		
	Balaji Enclave 1st Cross Rd		1				1.00		
	Nisargha Layout 10th Main Rd		1				1.00		
	CRPF Compound Near Govt School Ananthapura		1				1.00		
	Mahalakshmi Layout Main Rd		1				1.00		
	Ambhabhavani Layout 6th Cross Rd		1				1.00		
	Hariraja Layout 3rd Cross Rd		1				1.00		
	Balaji Layout 4th Cross Rd		1				1.00		

77 ಮುಖ್ಯ ಅಭಿಯಂಶಕರು(ಯ.ಎ)

ಮುಖ್ಯ

ಯಂತ್ರಾಲಯ
ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ate

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Brundavana Layout 1st Main Rd 1st Cross		1				1.00		
	3rd Cross Adtiyanagaraa		1				1.00		
	Cauvery Layout 2nd Main Rd		1				1.00		
			1				1.00		
							22.00	292.09	6425.98
	Approved Amount	292.09							
16	Providing wrought mild steel (galvanized) GI collar confirming to IS 1239-II, 1991 with latest amendments if any For 50 mm dia GI collar(P.129, I.No-11.6.6) Vol-5 BWSSB.SR 2023-24								
		Each							
	1st Main Rd Maruthi Layout		56				56.00		
	Ambha Bhavani Nagara 2nd Main 2nd Cross		53				53.00		
	1st Main Rd Vijaya Bank Layout		54				54.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		51				51.00		
	1st Main Ayyappa Layout		54				54.00		
	Burial Ground Vishwanagara Main Rd		44				44.00		
	1st Main Chandrappa Layout		55				55.00		
	9th Main 4th Cross Rd Adtiyanagara		56				56.00		
	1st Main Rd Eshwari Layout		42				42.00		
	Anugraha Layout[Avekanagar Layout]		56				56.00		
			48				48.00		
	Balaji Enclave 1st Cross Rd		53				53.00		
	Nisargha Layout 10th Main Rd		52				52.00		
	CRPF Compound Near Govt School Ananthapura		51				51.00		
	Mahalakshmi Layout Main Rd		47				47.00		
	Ambhabhavani Layout 6th Cross Rd		52				52.00		
	Hariraja Layout 3rd Cross Rd		56				56.00		
	Balaji Layout 4th Cross Rd		49				49.00		
	Brundavana Layout 1st Main Rd 1st Cross		49				49.00		
	3rd Cross Adtiyanagaraa		54				54.00		
	Cauvery Layout 2nd Main Rd		49				49.00		
			48				48.00		
							1129.00	292.09	329769.61
	Approved Amount	292.09							
17	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI hexagonal nipple confirming to IS 1239-II, 1991 with latest amendments if any. (P.132, I.No-11.14.6) Vol-5 BWSSB.SR								
		Each							
	For Bore Well								
	1st Main Rd Maruthi Layout		2				2.00		
	Ambha Bhavani Nagara 2nd Main		2				2.00		
	1st Main Rd Vijaya Bank Layout		2				2.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		2				2.00		
	1st Main Ayyappa Layout		2				2.00		
	Burial Ground Vishwanagara Main Rd		2				2.00		
	1st Main Chandrappa Layout		2				2.00		

Sl No	Description of work	Unit	Measurement				Qty	Rate	
			No.	L	B	D			
	9th Main 4th Cross Rd Adtiyanagara		2				2.00		
	1st Main Rd Eshwari Layout		2				2.00		
	Anugraha Layout[Avekanagar Layout]		2				2.00		
	Balaji Enclave 1st Cross Rd		2				2.00		
	Nisargha Layout 10th Main Rd		2				2.00		
	CRPF Compound Near Govt School		2				2.00		
	Ananthapura		2				2.00		
	Mahalakshmi Layout Main Rd		2				2.00		
	Ambhabhavani Layout 6th Cross Rd		2				2.00		
	Hariraja Layout 3rd Cross Rd		2				2.00		
	Balaji Layout 4th Cross Rd		2				2.00		
	Brundavana Layout 1st Main Rd 1st Cross		2				2.00		
	3rd Cross Adtiyanagaraa		2				2.00		
	Cauvery Layout 2nd Main Rd		2				2.00		
			2				2.00		
			2				2.00		
			2				2.00		
	Approved Amount						44.00	233.02	10252.88

18 Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI elbow confirming to IS 1239-II, 1991 with latest amendments if any for: (P.129, I.No-11.7.6) Vol-5 BWSSB.SR 2023-24

For Bore Well	Each								
1st Main Rd Maruthi Layout		3							
Ambha Bhavani Nagara 2nd Main		3				3.00			
1st Main Rd Vijaya Bank Layout		3				3.00			
1st Main Rd Annapurneshwari		3				3.00			
Nagara[Opp To Sambram Clg]		3				3.00			
1st Main Ayyappa Layout		3				3.00			
Burial Ground Vishwanagara Main Rd		3				3.00			
1st Main Chandrappa Layout		3				3.00			
9th Main 4th Cross Rd Adtiyanagara		3				3.00			
1st Main Rd Eshwari Layout		3				3.00			
Anugraha Layout[Avekanagar Layout]		3				3.00			
Balaji Enclave 1st Cross Rd		3				3.00			
Nisargha Layout 10th Main Rd		3				3.00			
CRPF Compound Near Govt School		3				3.00			
Ananthapura		3				3.00			
Mahalakshmi Layout Main Rd		3				3.00			
Ambhabhavani Layout 6th Cross Rd		3				3.00			
Hariraja Layout 3rd Cross Rd		3				3.00			
Balaji Layout 4th Cross Rd		3				3.00			
Brundavana Layout 1st Main Rd 1st Cross		3				3.00			
3rd Cross Adtiyanagaraa		3				3.00			
Cauvery Layout 2nd Main Rd		3				3.00			
		3				3.00			
		3				3.00			
Approved Amount		292.09				66.00	292.09	19277.94	

77 ಮುಖ್ಯ ಅಭಿಯಂಶಕರು(ಯ.ಪ)

೩೬ (೧೫)

ಮುಖ್ಯ ವಿಭಾಗೀಯ ಅಧಿಕಾರಿ
ಬಹಳ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
19	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100 V as per IS-694:2010. 3C x 6 mm ² (P.7, I.No-2.6.3) Vol-VI [PWD Ele S.R								
		Mtr							
	1st Main Rd Maruthi Layout		2	338.00			676.00		
	Ambha Bhavani Nagara 2nd Main		2	317.00			634.00		
	1st Main Rd Vijaya Bank Layout		2	326.00			652.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		2	310.00			620.00		
	1st Main Ayyappa Layout		2	326.00			652.00		
	Burial Ground Vishwanagara Main Rd		2	265.00			530.00		
	1st Main Chandrappa Layout		2	330.00			660.00		
	9th Main 4th Cross Rd Adtiyanagara		2	341.00			682.00		
	1st Main Rd Eshwari Layout		2	240.00			480.00		
	Anugraha Layout[Awekanagar Layout		2	340.00			680.00		
			2	300.00			600.00		
	Balaji Enclave 1st Cross Rd		2	323.00			646.00		
	Nisargha Layout 10th Main Rd		2	315.00			630.00		
	CRPF Compound Near Govt School Ananthapura		2	310.00			620.00		
	Mahalakshmi Layout Main Rd		2	283.00			566.00		
	Ambhabhavani Layout 6th Cross Rd		2	315.00			630.00		
	Hariraja Layout 3rd Cross Rd		2	336.00			672.00		
	Balaji Layout 4th Cross Rd		2	300.00			600.00		
	Brundavana Layout 1st Main Rd 1st Cross		2	298.00			596.00		
	3rd Cross Adtiyanagaraa		2	325.00			650.00		
	Cauvery Layout 2nd Main Rd		2	298.00			596.00		
			2	280.00			560.00		
							13632.00	243.66	3321573.12
	Approved Amount	243.66							
20	Labour charges for Erection, Electrification and commissioning of Pump sets, including aligning and balancing of all items including supply and erection of two pair of supporting clamps, bore well caps, cable clips and water tight gland cable protectors, bolts, nuts, valve and gauges, tools and equipments etc., involved in the job as per specifications, with necessary tests as per specifications, with testing of as per instructions of engineer incharge of work. (P.156, I.No-13.32) Vol-5 BWSSB.SR								
		Job							
	For Bore Well								
	1st Main Rd Maruthi Layout		1				1.00		
	Ambha Bhavani Nagara 2nd Main		1				1.00		
	1st Main Rd Vijaya Bank Layout		1				1.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1				1.00		
	1st Main Ayyappa Layout		1				1.00		
	Burial Ground Vishwanagara Main Rd		1				1.00		
	1st Main Chandrappa Layout		1				1.00		
	9th Main 4th Cross Rd Adtiyanagara		1				1.00		
	1st Main Rd Eshwari Layout		1				1.00		
	Anugraha Layout[Awekanagar Layout		1				1.00		

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Balaji Enclave 1st Cross Rd		1				1.00		
	Nisargha Layout 10th Main Rd		1				1.00		
	CRPF Compound Near Govt School Ananthapura		1				1.00		
	Mahalakshmi Layout Main Rd		1				1.00		
	Ambhabhavani Layout 6th Cross Rd		1				1.00		
	Hariraja Layout 3rd Cross Rd		1				1.00		
	Balaji Layout 4th Cross Rd		1				1.00		
	Brundavana Layout 1st Main Rd 1st Cross		1				1.00		
	3rd Cross Adtiyanagaraa		1				1.00		
	Cauvery Layout 2nd Main Rd		1				1.00		
			1				1.00		
			1				1.00		
	Approved Amount	7110.89					22.00	7110.89	156439.58
21	Labour charges for erection of outdoor type panel board and meter board units with all necessary materials and labour, tools and equipments including providing cement concrete foundation bed etc., complete as per specification, with testing of as per instructions of engineer incharge of work. (P.156, I.No-13.34) Vol-5 BWSSB.SR 2023-24								
	For Bore Well	Job							
	1st Main Rd Maruthi Layout		1				1.00		
	Ambha Bhavani Nagara 2nd Main		1				1.00		
	1st Main Rd Vijaya Bank Layout		1				1.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1				1.00		
	1st Main Ayyappa Layout		1				1.00		
	Burial Ground Vishwanagara Main Rd		1				1.00		
	1st Main Chandrappa Layout		1				1.00		
	9th Main 4th Cross Rd Adtiyanagara		1				1.00		
	1st Main Rd Eshwari Layout		1				1.00		
	Anugraha Layout[Avekanagar Layout		1				1.00		
			1				1.00		
	Balaji Enclave 1st Cross Rd		1				1.00		
	Nisargha Layout 10th Main Rd		1				1.00		
	CRPF Compound Near Govt School Ananthapura		1				1.00		
	Mahalakshmi Layout Main Rd		1				1.00		
	Ambhabhavani Layout 6th Cross Rd		1				1.00		
	Hariraja Layout 3rd Cross Rd		1				1.00		
	Balaji Layout 4th Cross Rd		1				1.00		
	Brundavana Layout 1st Main Rd 1st Cross		1				1.00		
	3rd Cross Adtiyanagaraa		1				1.00		
	Cauvery Layout 2nd Main Rd		1				1.00		
			1				1.00		
			1				1.00		
	Approved Amount	1586.28					22.00	1586.28	34898.16
22	1.1 kV, XLPE or Heat resistant PVC insulated, PVC extruded Inner Seath Armoured LTUG Cable as per IS-1554 (Part-1) or IS-7098 Part-1, Armouring strip thickness and resistivity as per IS-3975 16 Sqmm, 4 Core, (11 GI Strips - 4 x 0.8 mm) (P.13, Sl. no-201, I.No-32.05) Vol-VI ESCOM.SR [CSR-2023-24]								

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	For Bore Well	Km							
	1st Main Rd Maruthi Layout		1	14.00			14.00		
	Ambha Bhavani Nagara 2nd Main		1	6.00			6.00		
	1st Main Rd Vijaya Bank Layout		1	21.00			21.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	11.00			11.00		
	1st Main Ayyappa Layout		1	7.00			7.00		
	Burial Ground Vishwanagara Main Rd		1	100.00			100.00		
	1st Main Chandrappa Layout		1	9.00			9.00		
	9th Main 4th Cross Rd Adtiyanagara		1	15.00			15.00		
	1st Main Rd Eshwari Layout		1	10.00			10.00		
	Anugraha Layout[Avekanagar Layout		1	18.00			18.00		
			1	18.00			18.00		
	Balaji Enclave 1st Cross Rd		1	11.00			11.00		
	Nisargha Layout 10th Main Rd		1	6.50			6.50		
	CRPF Compound Near Govt School Ananthapura		1	56.40			56.40		
	Mahalakshmi Layout Main Rd		1	6.00			6.00		
	Ambhabhavani Layout 6th Cross Rd		1	9.00			9.00		
	Hariraja Layout 3rd Cross Rd		1	6.40			6.40		
	Balaji Layout 4th Cross Rd		1	12.90			12.90		
	Brundavana Layout 1st Main Rd 1st Cross		1	5.00			5.00		
	3rd Cross Adtiyanagaraa		1	21.40			21.40		
	Cauvery Layout 2nd Main Rd		1	6.20			6.20		
			1	12.00			12.00		
							381.80		
	Approved Amount	141066.12					0.38	141066.12	53859.04
23	LABOUR For Stringing of 1.1 kV grade Aerial Bunched 3 Core cable of XLPE insulation of size (3x95) (Phase Conductor) + (1x70) (Insulated Messenger Neutral) + (1x16) (Street Light Control) (P.53, Sl. no-208, I.No-24.03) Vol-VI ESCOM.SR [CSR-2023-24]								
		Km							
	1st Main Rd Maruthi Layout		1	14.00			14.00		
	Ambha Bhavani Nagara 2nd Main		1	6.00			6.00		
	1st Main Rd Vijaya Bank Layout		1	21.00			21.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	11.00			11.00		
	1st Main Ayyappa Layout		1	7.00			7.00		
	Burial Ground Vishwanagara Main Rd		1	100.00			100.00		
	1st Main Chandrappa Layout		1	9.00			9.00		
	9th Main 4th Cross Rd Adtiyanagara		1	15.00			15.00		
	1st Main Rd Eshwari Layout		1	10.00			10.00		
	Anugraha Layout[Avekanagar Layout		1	18.00			18.00		
			1	18.00			18.00		
	Balaji Enclave 1st Cross Rd		1	11.00			11.00		
	Nisargha Layout 10th Main Rd		1	6.50			6.50		
	CRPF Compound Near Govt School Ananthapura		1	56.40			56.40		
	Mahalakshmi Layout Main Rd		1	6.00			6.00		

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Ambhabhavani Layout 6th Cross Rd		1	9.00			9.00		
	Hariraja Layout 3rd Cross Rd		1	6.40			6.40		
	Balaji Layout 4th Cross Rd		1	12.90			12.90		
	Brundavana Layout 1st Main Rd 1st Cross		1	5.00			5.00		
	3rd Cross Adtiyanagaraa		1	21.40			21.40		
	Cauvery Layout 2nd Main Rd		1	6.20			6.20		
			1	12.00			12.00		
							381.80		
	Approved Amount						0.38	32927.89	12571.87
24	Earthing: Supplying and fixing earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia (P.157, I.No-13.39)								
	For Bore Well	Job							
	1st Main Rd Maruthi Layout		1				1.00		
	Ambha Bhavani Nagara 2nd Main		1				1.00		
	1st Main Rd Vijaya Bank Layout		1				1.00		
	1st Main Rd Annapurneshwari		1				1.00		
	Nagara[Opp To Sambram Clg]		1				1.00		
	1st Main Ayyappa Layout		1				1.00		
	Burial Ground Vishwanagara Main Rd		1				1.00		
	1st Main Chandrappa Layout		1				1.00		
	9th Main 4th Cross Rd Adtiyanagara		1				1.00		
	1st Main Rd Eshwari Layout		1				1.00		
	Anugraha Layout[Avekanagar Layout]		1				1.00		
			1				1.00		
	Balaji Enclave 1st Cross Rd		1				1.00		
	Nisargha Layout 10th Main Rd		1				1.00		
	CRPF Compound Near Govt School Ananthapura		1				1.00		
	Mahalakshmi Layout Main Rd		1				1.00		
	Ambhabhavani Layout 6th Cross Rd		1				1.00		
	Hariraja Layout 3rd Cross Rd		1				1.00		
	Balaji Layout 4th Cross Rd		1				1.00		
	Brundavana Layout 1st Main Rd 1st Cross		1				1.00		
	3rd Cross Adtiyanagaraa		1				1.00		
	Cauvery Layout 2nd Main Rd		1				1.00		
			1				1.00		
			1				1.00		
	Approved Amount						22.00	4102.44	90253.68
25	Providing, Supplying and fixing suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc. with necessary materials and labour tools and equipments as per instructions of engineer incharge of work. 3½x6 Sam (P.156, I.No-13.38.1) Vol-5 BWSSB.SR 2023-24)								
		Each							

Rate

A No

Description of work

Unit

Measurement

Qty

Rate

Amount

No.

L

B

D

For Bore Well

1st Main Rd Maruthi Layout

1

1.00

Ambha Bhavani Nagara 2nd Main

1

1.00

1st Main Rd Vijaya Bank Layout

1

1.00

1st Main Rd Annapurneshwari

1

1.00

Nagara[Opp To Sambram Clg]

1

1.00

1st Main Ayyappa Layout

1

1.00

Burial Ground Vishwanagara Main Rd

1

1.00

1st Main Chandrappa Layout

1

1.00

9th Main 4th Cross Rd Adtiyanagara

1

1.00

1st Main Rd Eshwari Layout

1

1.00

Anugraha Layout[Avekanagar Layout]

1

1.00

1

1.00

Balaji Enclave 1st Cross Rd

1

1.00

Nisargha Layout 10th Main Rd

1

1.00

CRPF Compound Near Govt School Ananthapura

1

1.00

Mahalakshmi Layout Main Rd

1

1.00

Ambhabhavani Layout 6th Cross Rd

1

1.00

Hariraja Layout 3rd Cross Rd

1

1.00

Balaji Layout 4th Cross Rd

1

1.00

Brundavana Layout 1st Main Rd 1st Cross

1

1.00

3rd Cross Adtiyanagaraa

1

1.00

Cauvery Layout 2nd Main Rd

1

1.00

1

1.00

22.00

410.24

9025.28

Approved Amount

410.24

26

Supply and fixing polished wood board made of not less than 15mm thick plank on both sides of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws 20" x 20" x 2.5" (P.14, I.No-5.6.6) Vol-VI [PWD Ele S.R 2023-24]

Nos

For Bore Well

1st Main Rd Maruthi Layout

1

1.00

Ambha Bhavani Nagara 2nd Main

1

1.00

1st Main Rd Vijaya Bank Layout

1

1.00

1st Main Rd Annapurneshwari

1

1.00

Nagara[Opp To Sambram Clg]

1

1.00

1st Main Ayyappa Layout

1

1.00

Burial Ground Vishwanagara Main Rd

1

1.00

1st Main Chandrappa Layout

1

1.00

9th Main 4th Cross Rd Adtiyanagara

1

1.00

1st Main Rd Eshwari Layout

1

1.00

Anugraha Layout[Avekanagar Layout]

1

1.00

1

1.00

Balaji Enclave 1st Cross Rd

1

1.00

Nisargha Layout 10th Main Rd

1

1.00

CRPF Compound Near Govt School Ananthapura

1

1.00

Sl No	Description of work	Unit	Measurement				Qty	Rate	
			No.	L	B	D			
	Mahalakshmi Layout Main Rd		1				1.00		
	Ambhabhavani Layout 6th Cross Rd		1				1.00		
	Hariraja Layout 3rd Cross Rd		1				1.00		
	Balaji Layout 4th Cross Rd		1				1.00		
	Brundavana Layout 1st Main Rd 1st Cross		1				1.00		
	3rd Cross Adtiyanagaraa		1				1.00		
	Cauvery Layout 2nd Main Rd		1				1.00		
			1				1.00		
							22.00	324.35	7135.70
	Approved Amount	324.35							
27	Supplying fully automatic star-delta starter unit push button type with suitable wires, 3 contactors, one adjustable thermal timer mounted on a common base plate held in steel enclosure for use on 400/440 V 3 phase and wired after fixing to the existing wooden board for motor Above 12.5 HP upto 25 HP (P.14, I.No-5.2.2) Vol-VI IPWD Ele S.R 2023-24]								
		Nos							
	For Bore Well								
	1st Main Rd Maruthi Layout		1				1.00		
	Ambha Bhavani Nagara 2nd Main		1				1.00		
	1st Main Rd Vijaya Bank Layout		1				1.00		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1				1.00		
	1st Main Ayyappa Layout		1				1.00		
	Burial Ground Vishwanagara Main Rd		1				1.00		
	1st Main Chandrappa Layout		1				1.00		
	9th Main 4th Cross Rd Adtiyanagara		1				1.00		
	1st Main Rd Eshwari Layout		1				1.00		
	Anugraha Layout[Avekanagar Layout]		1				1.00		
			1				1.00		
	Balaji Enclave 1st Cross Rd		1				1.00		
	Nisargha Layout 10th Main Rd		1				1.00		
	CRPF Compound Near Govt School Ananthapura		1				1.00		
	Mahalakshmi Layout Main Rd		1				1.00		
	Ambhabhavani Layout 6th Cross Rd		1				1.00		
	Hariraja Layout 3rd Cross Rd		1				1.00		
	Balaji Layout 4th Cross Rd		1				1.00		
	Brundavana Layout 1st Main Rd 1st Cross		1				1.00		
	3rd Cross Adtiyanagaraa		1				1.00		
	Cauvery Layout 2nd Main Rd		1				1.00		
							22.00	8716.06	191753.32
	Approved Amount	8716.06							
28	Supply and delivery at site of brand new best make gate valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50 mm [P.154, I.No-13.24.1) Vol-5 BWSSB.SR 2023-24]								
		Each							
	For Bore Well								

Rate

A No

Description of work	Unit	Mesurement				Qty	Rate	Amount
		No.	L	B	D			
1st Main Rd Maruthi Layout		4				4.00		
Ambha Bhavani Nagara 2nd Main		6				6.00		
1st Main Rd Vijaya Bank Layout		4				4.00		
1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		6				6.00		
1st Main Ayyappa Layout		5				5.00		
Burial Ground Vishwanagara Main Rd		4				4.00		
1st Main Chandrappa Layout		5				5.00		
9th Main 4th Cross Rd Adtiyanagara		7				7.00		
1st Main Rd Eshwari Layout		4				4.00		
Anugraha Layout[Avekanagar Layout]		5				5.00		
		5				5.00		
Balaji Enclave 1st Cross Rd		3				3.00		
Nisargha Layout 10th Main Rd		5				5.00		
CRPF Compound Near Govt School Ananthapura		8				8.00		
Mahalakshmi Layout Main Rd		3				3.00		
Ambhabhavani Layout 6th Cross Rd		4				4.00		
Hariraja Layout 3rd Cross Rd		6				6.00		
Balaji Layout 4th Cross Rd		4				4.00		
Brundavana Layout 1st Main Rd 1st Cross		6				6.00		
3rd Cross Adtiyanagaraa		6				6.00		
Cauvery Layout 2nd Main Rd		5				5.00		
		4				4.00		
						109.00	1367.48	149055.32
Approved Amount	1367.48							

29 Supply and delivery at site of brand new best make non-return valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50 mm [P.154, I.No-13.25.1) Vol-5 BWSSB.SR 2023-24]

	Each							
For Bore Well								
1st Main Rd Maruthi Layout		4				4.00		
Ambha Bhavani Nagara 2nd Main		6				6.00		
1st Main Rd Vijaya Bank Layout		4				4.00		
1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		6				6.00		
1st Main Ayyappa Layout		5				5.00		
Burial Ground Vishwanagara Main Rd		4				4.00		
1st Main Chandrappa Layout		5				5.00		
9th Main 4th Cross Rd Adtiyanagara		7				7.00		
1st Main Rd Eshwari Layout		4				4.00		
Anugraha Layout[Avekanagar Layout]		5				5.00		
		5				5.00		
Balaji Enclave 1st Cross Rd		3				3.00		
Nisargha Layout 10th Main Rd		5				5.00		
CRPF Compound Near Govt School Ananthapura		8				8.00		
Mahalakshmi Layout Main Rd		3				3.00		
Ambhabhavani Layout 6th Cross Rd		4				4.00		

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Hariraja Layout 3rd Cross Rd		6						
	Balaji Layout 4th Cross Rd		4				6.00		
	Brundavana Layout 1st Main Rd 1st Cross		6				4.00		
	3rd Cross Adtiyanagaraa		6				6.00		
	Cauvery Layout 2nd Main Rd		5				6.00		
			4				5.00		
							4.00		
	Approved Amount		1367.48				109.00	1367.48	149055.32
30	Supply and delivery at site delivery of best indigenous brand new MCB (Miniature Circuit Breakers) of required capacity as per IS 88228/1978 and its latest amendments and with ISI Mark of 6/10/16/20/25/40 Amps with scalable box. [P.155, I.No-13.26) Vol-5 BWSSB.SR 2023-24]								
	For Bore Well	per 3 Poles							
	1st Main Rd Maruthi Layout		1						
	Ambha Bhavani Nagara 2nd Main		1				1.00		
	1st Main Rd Vijaya Bank Layout		1				1.00		
	1st Main Rd Annapurneshwari		1				1.00		
	Nagara[Opp To Sambram Clg]		1				1.00		
	1st Main Ayyappa Layout		1				1.00		
	Burial Ground Vishwanagara Main Rd		1				1.00		
	1st Main Chandrappa Layout		1				1.00		
	9th Main 4th Cross Rd Adtiyanagara		1				1.00		
	1st Main Rd Eshwari Layout		1				1.00		
	Anugraha Layout[Avekanagar Layout		1				1.00		
			1				1.00		
	Balaji Enclave 1st Cross Rd		1				1.00		
	Nisargha Layout 10th Main Rd		1				1.00		
	CRPF Compound Near Govt School Ananthapura		1				1.00		
	Mahalakshmi Layout Main Rd		1				1.00		
	Ambhabhavani Layout 6th Cross Rd		1				1.00		
	Hariraja Layout 3rd Cross Rd		1				1.00		
	Balaji Layout 4th Cross Rd		1				1.00		
	Brundavana Layout 1st Main Rd 1st Cross		1				1.00		
	3rd Cross Adtiyanagaraa		1				1.00		
	Cauvery Layout 2nd Main Rd		1				1.00		
			1				1.00		
			1				1.00		
	Approved Amount		1258.08				22.00	1258.08	27677.76
	PVC PIPELINE								

77 ಮುಖ್ಯ ಅಭಿಯಂಶರರು(ಯ.ಎ.)

೮೮ (೧೫೫)

ಮುಖ್ಯ ವ

ಯಲದೂರು ಪಾಲಿಕೆ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

149055.32

No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
31	Earth work excavation for pipelines/cables by Manual means upto 600 mm trench width, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, including dressing of excavated surfaces, disposing off or leveling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m. Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering and lift upto 1.5 m including cost of labour, tools, usage& other								
		Cum							
	For Pipeline								
	1st Main Rd Maruthi Layout		1	171.50	0.60	0.65	66.89		
	Ambha Bhavani Nagara 2nd Main		1	451.00	0.60	0.65	175.89		
	1st Main Rd Vijaya Bank Layout		1	51.00	0.60	0.65	19.89		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	56.00	0.60	0.65	21.84		
	1st Main Ayyappa Layout		1	10.00	0.60	0.65	3.90		
	Burial Ground Vishwanagara Main Rd		1	154.00	0.60	0.55	50.82		
	1st Main Chandrappa Layout		1	59.00	0.60	0.65	23.01		
	9th Main 4th Cross Rd Adtiyanagara		1	32.00	0.60	0.65	12.48		
	1st Main Rd Eshwari Layout		1	205.50	0.60	0.30	36.99		
	Anugraha Layout[Avekanagar Layout]		1	75.00	0.60	0.65	29.25		
			1	380.00	0.60	0.65	148.20		
	Balaji Enclave 1st Cross Rd		1	239.40	0.60	0.65	93.37		
	Nisargha Layout 10th Main Rd		1	274.50	0.60	0.65	107.06		
	CRPF Compound Near Govt School Ananthapura		1	158.00	0.60	0.30	28.44		
	Mahalakshmi Layout Main Rd		1	173.80	0.60	0.52	54.23		
	Ambhabhavani Layout 6th Cross Rd		1	263.70	0.60	0.65	102.84		
	Hariraja Layout 3rd Cross Rd		1	24.30	0.60	0.65	9.48		
	Balaji Layout 4th Cross Rd		1	124.40	0.60	0.65	48.52		
	Brundavana Layout 1st Main Rd 1st Cross		1	4.50	0.60	0.65	1.76		
			1	21.40	0.60	0.65	8.35		
	3rd Cross Adtiyanagaraa		1	585.30	0.60	0.65	228.27		
	Cauvery Layout 2nd Main Rd		7	5.00	2.00	0.30	21.00		
	Debris		2	6.00	3.40	0.30	12.24		
	Debris						1304.69	529.49	690817.98
	Approved Amount	529.49							
32	Providing and installing at site of work 6 Kg/m2: 63mm(weight of pipe -0.662 kg) P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, including jointing of approved type with all labour level and perfect linking at joints leak proof including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete. [P.120, I.No-								
		mtr							
							0.00	13.82	0.00
	For Pipeline								
	Approved Amount	13.82							

SI No	Description of work	Unit	Mesurement				Qty	Rate	SI No
			No.	L	B	D			
33	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications (PWD SR 2023-24 Vol -I Pg No 7 item no								
	For Pipeline	Cum							
	1st Main Rd Maruthi Layout		1	171.50	0.60	0.45	46.31		
	Ambha Bhavani Nagara 2nd Main		1	451.00	0.60	0.45	121.77		
	1st Main Rd Vijaya Bank Layout		1	51.00	0.60	0.45	13.77		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	56.00	0.60	0.45	15.12		
	1st Main Ayyappa Layout		1	10.00	0.60	0.45	2.70		
	1st Main Chandrappa Layout		1	65.00	0.60	0.45	17.55		
	9th Main 4th Cross Rd Adtiyanagara		1	32.00	0.60	0.45	8.64		
	1st Main Rd Eshwari Layout		1	205.50	0.60	0.30	36.99		
	Anugraha Layout[Avekanagar Layout		1	75.00	0.60	0.45	20.25		
	Balaji Enclave 1st Cross Rd		1	380.00	0.60	0.45	102.60		
	Nisargha Layout 10th Main Rd		1	239.40	0.60	0.45	64.64		
	Mahalakshmi Layout Main Rd		1	274.50	0.60	0.45	74.12		
	Ambhabhavani Layout 6th Cross Rd		1	108.00	0.60	0.45	29.16		
	Hariraja Layout 3rd Cross Rd		1	263.70	0.60	0.45	71.20		
	Balaji Layout 4th Cross Rd		1	24.30	0.60	0.45	6.56		
	Brundavana Layout 1st Main Rd 1st Cross		1	124.40	0.60	0.45	33.59		
	3rd Cross Adtiyanagaraa		1	4.50	0.60	0.45	1.22		
	Cauvery Layout 2nd Main Rd		1	21.40	0.60	0.45	5.78		
			1	585.30	0.60	0.45	158.03		
	Approved Amount	175.04					829.98	175.04	145279.70
	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density (V-III,								
	For Connecting borewell	Cum							
	1st Main Rd Maruthi Layout		1	171.50	1.00	0.20	34.30		
	Ambha Bhavani Nagara 2nd Main		1	451.00	1.00	0.20	90.20		
	1st Main Rd Vijaya Bank Layout		1	51.00	1.00	0.20	10.20		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	56.00	1.00	0.20	11.20		
	1st Main Ayyappa Layout		1	10.00	1.00	0.20	2.00		
	Burial Ground Vishwanagara Main Rd		1	154.00	0.75	0.15	17.33		
	1st Main Chandrappa Layout		1	59.00	1.00	0.20	11.80		
	9th Main 4th Cross Rd Adtiyanagara		1	34.00	1.00	0.20	6.80		
	1st Main Rd Eshwari Layout		1	205.50	0.75	0.20	30.83		
	Anugraha Layout[Avekanagar Layout		1	75.00	1.00	0.20	15.00		
	Balaji Enclave 1st Cross Rd		1	380.00	1.00	0.20	76.00		
	Nisargha Layout 10th Main Rd		1	239.40	1.00	0.20	47.88		
	CRPF Compound Near Govt School Ananthapura		1	274.50	1.00	0.20	54.90		
	Mahalakshmi Layout Main Rd		1	158.00	0.75	0.20	23.70		
			1	108.00	1.00	0.20	21.60		

34

77 ಮುಖ್ಯ ಅಭಿಯಂಶಕರು (ಮುಖ್ಯ ಅಭಿಯಂಶಕರು)

ಬಹು ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ


Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
			1	65.80	0.90	0.20	11.84		
	Ambhabhavani Layout 6th Cross Rd		1	263.70	1.00	0.20	52.74		
	Hariraja Layout 3rd Cross Rd		1	24.30	1.00	0.20	4.86		
	Balaji Layout 4th Cross Rd		1	124.40	1.00	0.20	24.88		
	Brundavana Layout 1st Main Rd 1st Cross		1	10.00	1.00	0.20	2.00		
	3rd Cross Adtiyanagaraa		1	24.50	1.00	0.20	4.90		
	Cauvery Layout 2nd Main Rd		1	178.30	1.00	0.20	35.66		
	Cauvery Layout 3rd Main Rd		1	171.00	0.95	0.20	32.49		
			1	236.00	0.95	0.20	44.84		
							667.94	2799.44	1869869.15
	Approved Amount	2799.44							
	Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects (V-III),								
	For BC	Cum							
	1st Main Rd Maruthi Layout		1	171.50	1.00	0.04	6.86		
	Ambha Bhavani Nagara 2nd Main		1	451.00	1.00	0.04	18.04		
	1st Main Rd Vijaya Bank Layout		1	51.00	1.00	0.04	2.04		
	1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]		1	56.00	1.00	0.04	2.24		
	1st Main Ayyappa Layout		1	10.00	1.00	0.04	0.40		
	1st Main Chandrappa Layout		1	59.00	1.00	0.04	2.36		
	1st Main Chandrappa Layout		1	34.00	1.00	0.04	1.36		
35	9th Main 4th Cross Rd Adtiyanagara		1	75.00	1.00	0.04	3.00		
	Anugraha Layout[Avekanagar Layout]		1	380.00	1.00	0.04	15.20		
			1	239.40	1.00	0.04	9.58		
	Balaji Enclave 1st Cross Rd		1	274.50	1.00	0.04	10.98		
	Nisargha Layout 10th Main Rd		1	108.00	1.00	0.04	4.32		
	Mahalakshmi Layout Main Rd		1	263.70	1.00	0.04	10.55		
	Ambhabhavani Layout 6th Cross Rd		1	24.30	1.00	0.04	0.97		
	Hariraja Layout 3rd Cross Rd		1	124.40	1.00	0.04	4.98		
	Balaji Layout 4th Cross Rd		1	10.00	1.00	0.04	0.40		
	Brundavana Layout 1st Main Rd 1st Cross		1	24.50	1.00	0.04	0.98		
	3rd Cross Adtiyanagaraa		1	178.30	1.00	0.04	7.13		
	Cauvery Layout 2nd Main Rd		1	171.00	0.95	0.04	6.50		
	Cauvery Layout 3rd Main Rd						107.88	11983.00	1292750.01
	Approved Amount	11983.00							
	SUPPLYING WATER THROUGH TANKERS (B)								
36	Water Tanker (6 KL) (2023-24 SR Vol-I Sl.No-135 P.No-A47) (6KL/hr-725, For 10hr 725*10=7250 inclusive of GST)								
		Day					0	7931.00	0.00


Sl No	Description of work	Unit	Measurement				Qty	Rate	
			No.	L	B	D			
37	Providing Causal Labours (Unskilled mazdoor Heavy) (PWD SR 2021-22 Page No-A49. V-I)	7931.00							
	Day								
38	Water Charges as BWSSB Rates 6000 ltr Tanker. Approved Rates By BWSSB	703.87					0	703.87	0.00
	Loads								
	Approved Amount	537.00					0	537.00	0.00
	EIRL								
Providing PVC ringtite pipes conforming to IS 4985:2000 with latest amendments and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading unloading at both destinations and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approved type, with all labour with all lead & lift including encasing the pipe around to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc. complete and giving necessary hydraulic test to the required pressure as per ISS (Contractor will make his own arrangements for procuring water for testing) etc. complete For: PVC pipes 63mm dia., 6 kg/sqcm & class 3(I.No-10.1.4, Page No-113 BWSSB VOL-5 SR2023-24)									
For Pipeline		Mtr							
1st Main Rd Maruthi Layout			1	171.50				171.50	
Ambha Bhavani Nagara 2nd Main			1	451.00				451.00	
1st Main Rd Vijaya Bank Layout			1	51.00				51.00	
1st Main Rd Annapurneshwari Nagara[Opp To Sambram Clg]			1	56.00				56.00	
1st Main Ayyappa Layout			1	10.00				10.00	
Burial Ground Vishwanagara Main Rd			1	154.00				154.00	
1st Main Chandrappa Layout			1	59.00				59.00	
9th Main 4th Cross Rd Adtiyanagara			1	34.00				34.00	
1st Main Rd Eshwari Layout			1	205.50				205.50	
Anugraha Layout[Awekanagar Layout]			1	75.00				75.00	
Balaji Enclave 1st Cross Rd			1	380.00				380.00	
Nisargha Layout 10th Main Rd			1	321.40				321.40	
CRPF Compound Near Govt School Ananthapura			1	274.50				274.50	
Mahalakshmi Layout Main Rd			1	158.00				158.00	
Ambhabhavani Layout 6th Cross Rd			1	173.80				173.80	
Hariraja Layout 3rd Cross Rd			1	293.70				293.70	
Balaji Layout 4th Cross Rd			1	24.30				24.30	
Brundavana Layout 1st Main Rd 1st Cross			1	124.40				124.40	
3rd Cross Adtiyanagaraa			1	4.50				4.50	
Cauvery Layout			1	21.40				21.40	
2nd Main Rd			2	178.30				356.60	
3rd Main Rd			2	171.00				342.00	
			1	236.00				236.00	


77) ಮುಖ್ಯ ಅಭಿಯಂಶಕರು -
 ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Basic Rate						3977.60	176.13	700558.58
	10% Area Weightage	161.00							
	Total	16.10							
0.00	TP 0.55%	177.10							
	Total	0.97							
		176.13							
	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separatel(V-III Page No.12, Item No.2.19 of CSR 2023-24)								
	For Pipeline	Cum							
	Burial Ground Vishwanagara Main Rd		1	43.00	0.60	0.30	7.74		
	1st Main Rd Eshwari Layout		1	205.50	0.60	0.30	36.99		
	CRPF Compound Near Govt School		1	158.00	0.60	0.30	28.44		
E2	Mahalakshmi Layout Main Rd								
	5th A Main Rd								
	3rd A Main Rd		1	29.00	0.60	0.30	5.22		
	Cauvery Layout		1	36.80	0.60	0.30	6.62		
	1st Cross Rd								
	2nd Cross Rd		1	35.00	0.60	0.30	6.30		
	3rd Cross Rd		1	67.00	0.60	0.30	12.06		
	4th Cross Rd		1	67.00	0.60	0.30	12.06		
			1	67.00	0.60	0.30	12.06		
	Basic Rate	563.00					127.49	615.89	78522.77
	10% Area Weightage	56.30							
	Total	619.30							
	TP 0.55%	3.41							
	Total	615.89							
	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383:2016:, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, primer, sealant, curing of concrete slabs for 14-days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete. as per the directions of the Engineer-in-charge of the work.(V-III, P.No-148,I No-16.28, CSR 2023-24).								
	For Pipeline	Cum							
E3	Burial Ground Vishwanagara Main Rd		1	154.00	0.75	0.15	17.33		
	1st Main Rd Eshwari Layout		1	205.50	0.75	0.15	23.12		
	CRPF Compound Near Govt School		1	158.00	0.75	0.15	17.78		
	Mahalakshmi Layout Main Rd								
	5th A Main Rd		1	29.00	0.75	0.15	3.26		

SI No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	3rd A Main Rd								
	Cauvery Layout		1	36.80	0.75	0.15	4.14		
	1st Cross Rd								
	2nd Cross Rd		1	35.00	0.90	0.15	4.73		
	3rd Cross Rd		1	67.00	0.90	0.15	9.05		
	4th Cross Rd		1	67.00	0.90	0.15	9.05		
			1	67.00	0.90	0.15	9.05		
	Basic Rate	6754.00					97.48	7388.54	720243.95
	10% Area Weightage	675.40							
	Total	7429.40							
	TP 0.55%	40.86							
	Total	7388.54							
Total Construction Cost									24731232.45
GST 18%									4451621.84
Bescom Charges									484000.00
PMC Charges									295000.00
Sub Total Including GST									29961854.29


Assistant Engineer


Assistant Executive Engineer
ಕರ್ನಾಟಕ ರಾಜ್ಯ ಸಾರ್ವಜನಿಕ ಕಾರ್ಯದರ್ಶಿ
ಯಲಹಂಕರ ಉಪನಗರ ಉಪವಿಭಾಗ,
ಇ.ಇ.ಎಂ.ಓ. ಬೆಂಗಳೂರು-108


Executive Engineer
Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE - 560064

Technical Sanction
Accorded For Rs. 29961854.29
Head of A/C. D. 2803
CER NO 143 Dt. 24.05.24



